

POTPRESS · CALCULATION NOTE

PotPress sizing and first-principles checks

Design Molecule Lab · designmolecule.com

DOCUMENT CONTROL

Document ID	PPR-CAL-001	Version	0.9
Status	Draft	Date	2026-10-02
Author	Amish Chadha	License	CERN-OHL-S-2.0
Project TRL	TRL 3 Proof of concept		
Repository	github.com/BoujeeEnjinia1701/potpress		
Source	docs/04-calcs/01-sizing.md @ uncommitted		

REVISION HISTORY

Version	Date	Author	Change
0.9	2026-10-02	Amish Chadha	Approved follow-ups carried out: mean pressure at 2 t in Table 3; pump slot shield costed; ISO 13857 desk check (section 15); R9 at risk to not met on paper; cost \$1,149, \$89 over the value-engineering target
0.8	2026-10-02	Amish Chadha	Decisions of 2026-10-02: R9 status at risk until the pump slot shield is designed; working force as a process setting found in trials
0.7	2026-10-01	Amish Chadha	Budget treated as a value-engineering target; R10 reported against the target
0.6	2026-09-30	Amish Chadha	Design for construction (PPR-DDR-004); new checks for the male flange on the stop, M16 joints, rails, lead screw float, demolding tilt; masses and costs from the constructable model; R10 not met on paper
0.5	2026-09-27	Amish Chadha	Cost overrun decided by Amish on 2026-09-27; budget \$1,060, R10 met on paper with a \$9 margin

0.4	2026-09-26	Amish Chadha	Guarded version costs (PPR-DDR-003)
0.3	2026-09-26	Amish Chadha	Budget top-up approved by Amish; budget \$990, R10 met on paper with a \$6 margin
0.2	2026-09-25	Amish Chadha	Recommendations accepted by Amish (DDR-002); bolted upright joints, hinged rail extension, R3 at 10 t, R11 rack 0.8 x 0.8 m, budget \$930, cost \$984
0.1	2026-09-25	Amish Chadha	First TRL 3 sizing note (geometry, mix, frame and pin, deflection, travel, cycle, alignment, patterns, QC gauge, masses, tipping, cost) against every requirement

PotPress sizing and first-principles checks

On paper the press forms the reference filter, opens far enough, keeps up the output and stays strong at 1.5 times the jack rating, but it is heavier and dearer than the TRL 2 estimates said. With the recommendations Amish accepted on 2026-09-25 (PPR-DDR-002) and the guarded version he decided on 2026-09-26 (PPR-DDR-003), ten of the twelve requirements are met on paper and two are at risk. The value-engineering target stood at \$990 on 2026-09-26, which the \$984 BOM was within; the fixed guards and interlocked front gate then added \$67, and the target was set at \$1,060 on 2026-09-27 (PPR-DDR-003), so R10 was within the target at \$1,051 with a \$9 (0.8 %) margin. Making the design constructable on 2026-09-30 (PPR-DDR-004) added the parts a build needs and raised the parts cost to \$1,143, \$83 (7.8 %) over the \$1,060 value-engineering target, so R10 was over the target by \$83; the design decisions register lists the cost drivers and savings worth trying. The fixed inner shield behind the pump slot, decided by Amish on 2026-10-02, adds \$6 (now \$1,149, \$89 over the target), and the ISO 13857 desk check done the same day (section 15) found guard openings that fall short of the standard, so R9 is not met on paper until the guard changes it proposes are decided and made. R3 is now judged at the 10 t working force with the molds closing on a metal stop (0.61 mm), R11 allows 0.8 x 0.8 m for the QC rack and a hinged rail extension keeps the press 655 mm deep, and bolting the four upright joints keeps every part under 40 kg (R8). The calculations also found three TRL 2 errors that the model now corrects: the base beam (a single UPN 100) would have been stressed to about 1,071 MPa, the two 30 mm load pins would have failed in bending (about 1,030 MPa), and solid aluminum molds would have weighed about 57 and 41 kg, so the molds are now cast shells.

Every number in this note is printed by `docs/04-calcs/sizing.py` (run from the repo root: `python docs/04-calcs/sizing.py`). The script reads the geometry from `PARAMS`, `SECTIONS` and `levels()` in `cad/src/model.py`, takes part masses from the model solids, and reads the prices from `bom/bom.csv`, so the model, the drawing PPR-DWG-001, the BOM and this note agree. All values are first-principles estimates; nothing here is measured.

■ 1. Assumptions

Table 1. Inputs. All are assumptions for a paper design unless marked as decided.

Input	Value	Basis
Architecture, lift, molds, frame, demolding, QC, band	As decided	PPR-DDR-001 items 1 to 8
R3 basis, rack area, bolted joints, single pin with interlock, budget \$1,060, lead-free scrap	As decided	PPR-DDR-001 items 10 to 15; PPR-DDR-002 (budget topped up to \$990 by Amish, 2026-09-26); PPR-DDR-003 (budget raised to \$1,060 by Amish, 2026-09-27)
Joint bolts and hinges	M20 x 150 grade 8.8 with nut and washers \$3.00 each, 16 in all; rail extension hinges and stop lugs \$10	Regional retail estimate
Reference filter	Inner rim 280 mm, inner floor 230 mm, inner depth 240 mm, wall 15 mm normal to the surface, flat rim 345 mm x 15 mm	R1; Potters for Peace form of about 280 by 250 mm
Mix	59 % clay, 16 % rice husk, 25 % water by mass; particle densities 2,600, 1,400 and 1,000 kg/m ³ ; 3 % entrapped air	RDI-C recipe in Rayner (2009) ; densities typical
Process losses	Trim 10 % of pressed mass (recycled); 2 % water left after drying; clay loss on ignition 10 %; 10 % QC rejects	Estimates
Working force	5 to 10 t (49 to 98 kN); design load 1.5 x 20 t = 294 kN	Not sourced; see section 3
Steel	S275, yield 275 MPa, allowable 165 MPa at the jack rating; E = 200 GPa, G = 80 GPa	Standard values
Load pin	42CrMo4 quenched and tempered, yield 650 MPa	Typical for 40 to 100 mm bar
Cast aluminum	Al-Si scrap alloy, yield about 90 MPa as cast, density 2,680 kg/m ³	Conservative
Welds	E6013, 6 mm fillets, allowable 129 MPa on the throat (0.3 x 430 MPa)	Common stick electrode
Jack	60 mm ram, 16 mm pump piston with 22 mm stroke, lever ratio 30	Typical 20 t bottle jack; not from a data sheet
Casting tolerance	ISO 8062 CT10 for about 400 mm: ±0.8 mm on radius, plus ±0.3 mm print error and ±0.5 mm core shift	Sand casting typical
Loose charge	1.5 kg/L as placed	Estimate
Prices (2026)	Steel \$1.30/kg; scrap aluminum \$2.00/kg, 1.35 kg poured per kg of casting, foundry fee \$1.50/kg; PLA \$20/kg at 25 % of solid mass	Indicative regional prices

■ 2. Filter geometry and mass

The reference filter holds 12.30 L to the brim and 9.91 L to 40 mm below the rim, which matches R1 and the 9.84 L Cambodian filter. The wall is tapered at 5.9°, so a 15 mm normal wall moves the outer surface 15.1 mm out; the outer floor radius is 128.5 mm and the outer rim radius 155.1 mm, over an outer depth of 255 mm.

Table 2. Pot geometry and masses.

Quantity	Value	Basis
Wall and rim volume	4.14 L	Outer frustum minus inner, plus rim ring
Mix density	1.69 kg/L solid; 1.64 kg/L pressed	Rule of mixtures, 3 % air; husk is 19 % by volume
Pressed pot	6.79 kg	4.14 L x 1.64 kg/L
Charge	7.47 kg	Plus 0.68 kg trim
Dried pot	5.20 kg	Loses 1.60 kg of water
Fired pot	3.61 kg	Loses 1.59 kg (husk burnout, clay loss on ignition, residual water)
Passes QC	3.25 kg per pot made	0.36 kg rejected at 10 %

The charge of about 7.5 kg is below the 8 to 9.5 kg that factories report (Rayner, 2009). Either their walls are thicker than 15 mm, their filters are larger, or they trim more. A partner factory's own mold dimensions should replace the reference filter before TRL 4.

■ 3. Force and pressure

The pressing force needed for a well-consolidated wall was still not found. Henry, Maley and Mehta (2013) note that the Potters Without Borders press uses a 20 t jack, but their own low-cost press forms round-bottom filters with a 2 t car jack (Henry, Maley and Mehta, *IJSLE* 8 (1), 2013). The working force may therefore be well below the assumed 5 to 10 t. The frame is sized for the full jack rating either way. Decided by Amish on 2026-10-02: every structural check stays at the full 20 t jack, and the working force is a process setting found in pressing trials with a partner factory, starting near 2 t and stepping up.

Table 3. Mean pressure over the 0.0935 m² projected area of the pot.

Force	kN	Mean pressure
2 t (start of pressing trials)	19.6	0.21 MPa
5 t	49.0	0.52 MPa
10 t	98.1	1.05 MPa
20 t (rating)	196.2	2.10 MPa
30 t (1.5 x rating)	294.3	3.15 MPa

Pressing trials start near 2 t, where the mean pressure on the pot is 0.21 MPa, a fifth of the 1.05 MPa at 10 t. That is the starting reference for the trials; the force is then stepped up until the wall is well consolidated.

■ 4. Frame and load path

The press force runs from the jack through the platen, the female mold, the pot and the male mold into the stem, across one load pin into the top crossbeam, down both uprights in tension and back through the base beam to the jack. Each beam is two UPN 160 channels with a 104 mm gap between the webs (the 100 mm uprights plus a 2 mm shim each side, PPR-DDR-004); the uprights (two UPN 100 channels back to back, 100 x 100 mm) and the stem sit in that gap. The TRL 2 base was a single UPN 100 (41 cm³); under the same 44 kN·m it would reach about 1,071 MPa, so the base beam now matches the top beam.

Table 4. Stresses. Beam span 600 mm (upright centers), center load.

Item	10 t	20 t (rating)	30 t (design)	Limit
Beam bending (2 x UPN 160, 232 cm ³), top and base	63 MPa	127 MPa	190 MPa	165 at rating; 275 yield at design
Beam web shear	20 MPa	41 MPa	61 MPa	
Uprights, tension (2 x 2,700 mm ²)	18 MPa	36 MPa	54 MPa	
Load pin, 60 mm, bending (arm 39.25 mm)		182 MPa	272 MPa	650 yield
Load pin, shear (double)			52 MPa	
Pin bearing on web plus 12 mm doubler			126 MPa (327 MPa without doubler)	
Pin bearing on the stem pin block, less its 28 mm lead screw hole			79 MPa	
Web tear-out above the pin (38.5 mm ligament)			98 MPa	
Stem, SHS 90 x 8, compression			112 MPa	
Upright joint welds, welded option (556 mm of 6 mm fillet)			62 MPa	129
Upright joints as built, 4 x M16 10.9 in double shear per joint (thread in the shear plane)			117 MPa	400 resistance
Joint bolt bearing on beam web (7.5 mm) / upright flange (8.5 mm)			153 / 135 MPa	
Male mold flange, 45 mm, with all the force on the stop ring (ring cantilever from the plug at 140 mm radius)		41 MPa	62 MPa	about 90 yield
Male plug shell in compression / stop ring bearing / adapter disc on the plug floor			24 / 5.1 / 10.4 MPa	
Female steel base plate, 15 mm, across the rails		101 MPa	151 MPa	275 yield
Rails with the 6 mm deck, across the 104 mm gap between the platen webs		68 MPa	101 MPa	275 yield
Platen (2 x UPN 140), rails at ± 60 and ± 170 mm		65 MPa	98 MPa	
Female mold floor (30 mm, span 120 mm)	13 MPa	25 MPa	38 MPa	about 90 yield
Male mold tip plate (30 mm, radius 100 mm)	15 MPa	29 MPa	44 MPa	about 90 yield
Mold shell hoop, female / male	8 / 10 MPa	16 / 20 MPa	24 / 29 MPa	about 90 yield

The TRL 2 pair of 30 mm pins passes in shear (104 MPa) but not in bending: with the same web, gap and stem geometry each pin would see about 1,030 MPa. One 60 mm pin in quenched and tempered alloy steel passes with a factor of 2.5 on yield at the design load. It is a single load path, so the guard must include a pin-presence interlock (PPR-DDR-001 item 13, decided by Amish on 2026-09-25).

The mold stresses use the mean pressure; local pressure near the rim, where the clay extrudes, may be higher. Fatigue at about 20,000 cycles a year is not assessed at TRL 3.

Deflection between the molds

Table 5. Axial deflection that opens the gap between the molds, mm.

Contribution	10 t	20 t	30 t
Top beam (bending plus shear)	0.20	0.39	0.59
Base beam (bending plus shear)	0.20	0.39	0.59
Uprights	0.11	0.23	0.34
Stem	0.10	0.20	0.30
Platen	0.02	0.04	0.06
Pin allowance	0.03	0.07	0.10
Total	0.66	1.31	1.97

The v0.1 R3 target of less than 1 mm at 294 kN was not met. Shear deflection is about 40 % of each beam's share because the beams are short and deep, so a deeper section helps little: 2 x UPN 200 would still give 1.46 mm for 21.8 kg more steel. The wall thickness does not depend on this deflection if the molds close on a metal stop: the male flange lands on the female stop face outside the flash groove, and the rim thickness is set by the 15 mm counterbore. Amish accepted the recommendation on 2026-09-25 (PPR-DDR-001 item 10, PPR-DDR-002): R3 now judges deflection at the 10 t maximum working force, where it is 0.66 mm (0.61 mm before the stem was lengthened to reach down to the plug floor, PPR-DDR-004), so R3 is met on paper. Strength is still checked at 294 kN.

Checks added for construction (PPR-DDR-004)

- **Male flange on the stop.** The TRL 3 model's 25 mm flange, loaded at the stop ring and supported by a 180 mm adapter, would have reached about 487 MPa at 294 kN. The constructable plug carries the stem's disc on its floor and the flange as a 45 mm ring cantilevered from the plug wall: 41 MPa at 20 t and 62 MPa at 30 t with all the force on the stop, against about 90 MPa as-cast yield.
- **Joint bolts.** M16 grade 10.9 replaces M20 8.8, which did not fit the UPN 100 flange. The hole centre is 28 mm from the web, 22 mm from the flange tip (EN 1993-1-8 asks 21.6 mm for an 18 mm hole), and the 25 mm spacer tube inside the channel clears the web root radius by 1.0 mm. Double shear is 117 MPa at 30 t against a resistance of 400 MPa.
- **Lead screw.** The captive nut has 8 mm of free travel in its box; the pin has at most 2 mm of play in its bores, so the pin takes the press force before the nut can touch the box floor, and the screw carries only the slide's weight. A 28 mm hole down the pin block lets the fixed screw pass as the stem rises 200 mm; it reduces the pin's bearing length in the block from 90 to 62 mm (79 MPa at 30 t).

- **Demolding tilt.** With the carriage pulled out onto the tipping pins and the mold turned right over, about 51 kg sits 520 mm past the rail hinge: 260 N·m on the hinge, 10.8 kN on each 20 x 30 mm stop lug. Starting the tip needs about 283 N on the two lift handles together. The 12 mm tipping pins see about 180 MPa with a shock factor of 2, so they are bright medium-carbon bar (EN8 or 1045). The press still stands with 654 N·m to spare before the floor anchors are counted.

■ 5. Travel, jack and crank

A loose 7.5 kg charge at 1.5 kg/L forms a slug about 90 mm deep in the cavity, so the jack needs about 84 mm of pressing travel (slug depth less the 15 mm floor, plus 10 mm of approach). The model uses 110 mm, leaving 40 mm of the 150 mm jack stroke. To open, the male tip must rise 270 mm relative to the closed position (240 mm plug plus 30 mm clearance, R5); the jack retracts 110 mm and the crank lifts 200 mm, for 310 mm and a 70 mm clearance above the female rim. The female rim sits at 921 mm for loading.

The Tr24 x 5 lead screw needs 40 turns each way. It is self-locking (lead angle about 4° against a friction angle of about 8.5°), so the male mold cannot drop if the crank is released. The screw lifts only the male mold (17.9 kg) and its stem; it never carries the press force.

With the assumed jack, each pump stroke lifts the ram 1.56 mm, so closing takes about 70 strokes. The handle force is about 233 N at 10 t and 465 N at the 20 t rating (hydraulic pressure 69 MPa); the high value is reached only at the end of a stroke and only if the working force really is near the rating.

■ 6. Cycle and output

Table 6. Cycle with two operators.

Step	Time
Load charge and liner, slide carriage in	60 s
Crank male mold down (40 turns at 1.5 turns/s), insert pin	27 s
Pump to close (70 strokes at 1.2 s)	84 s
Dwell	15 s
Release	10 s
Pull pin, crank up	27 s
Slide out, tilt, demold and trim	90 s
Total	313 s (5.2 min)

That gives about 69 pots per 6 h of pressing, above the 50 in R4, but the margin rests on the pumping estimate.

■ 7. Alignment and wall evenness

The molds locate on two 16 mm hardened dowels in the female flange and two steel bushes in the male flange (PPR-DDR-004; this replaces the 390 mm turned lip, which needed a 420 mm lathe). The holes are drilled with the molds clamped together on printed 15 mm wall spacers, so the dowels hold the setting made with the spacers; the pin in its bush has 0.05 mm of diametral play. The carriage and stem clearances do not set the mold alignment. What remains is the accuracy of each mold's cavity relative to the other.

- As cast, each mold carries about ± 0.99 mm radial error (RSS of CT10, print error and core shift), so the wall varies by about ± 1.40 mm. R2 (± 1 mm) is not met as cast.
- Finished by hand to printed templates at ± 0.3 mm, the wall varies by about ± 0.44 mm and the molds are coaxial to about ± 0.44 mm, inside R2's ± 1 mm and 0.5 mm.

R2 is therefore **at risk**: it depends on hand finishing reaching ± 0.3 mm on a 400 mm casting without a lathe, which cannot be shown at TRL 3.

■ 8. Casting patterns (R7)

With a 1.3 % shrink allowance, the female pattern is 456 mm across by 274 mm tall and the male 456 mm by 289 mm. On a 250 mm printer each splits into four quadrants in two tiers, 16 segments in all, using about 5.4 kg of PLA at 25 % of solid mass. Both are flat-back patterns: each mold's inside opens at the flange face, so the sand forms its own core and no core box is needed (PPR-DDR-004). The patterns carry 3 mm to lap off the stop faces and the female base and 2° draft on the flange rims. No part needs a lathe; the stop faces are lapped on abrasive paper on float glass. Printing is within reach of a maker space; finishing the cast cavity to ± 0.3 mm by hand is not proven, so R7 is **at risk**.

■ 9. Flow-rate QC

Filled to 10 mm below the rim, the pot holds 11.69 L with a water surface of 0.0607 m².

Table 7. T-gauge scale.

Volume passed in 1 h	Level drop
0.1 L	1.7 mm
1.0 L	16.7 mm
2.5 L	42.6 mm
3.0 L	51.4 mm

A 0.1 L/h step is 1.69 mm near 1.0 L/h and 1.76 mm near 2.5 L/h, so printed 1 mm ticks resolve it; a 1 mm reading error is 0.061 L. The resolution meets R6; repeatability of ± 0.1 L/h depends on how the gauge is read and is to be shown later.

Water viscosity (Vogel equation) is 1.002, 0.890 and 0.797 mPa·s at 20, 25 and 30 °C, so flow changes by about 2.3 % per °C near 25 °C, and water at 30 °C flows 1.26 times as fast as water at 20 °C. To correct to 25 °C, multiply a reading by 1.125 at 20 °C and 0.895 at 30 °C (decided band, PPR-DDR-001 item 7).

Four 345 mm rims need at least 1.46 m in one row, or about 0.78 x 0.78 m in a 2 x 2 grid. The modeled rack is 780 x 780 x 720 mm (pot shelf raised so the hanging pots clear the 325 mm buckets by 35 mm, PPR-DDR-004), inside the 0.8 x 0.8 m that R11 now allows for the rack (decided by Amish, 2026-09-25, PPR-DDR-001 item 11).

■ 10. Masses and handling

Table 8. Masses from the model solids, kg (constructable model, PPR-DDR-004).

Item	Mass
1 Base beam, feet and jack plate	58.2 (base beam 34.2, jack plate 8.9, each foot 7.1, plus anchors and bolts)
2 Uprights	67.4 (29.4 per pair, plus spacer tubes, shims and 5.1 of M16 bolts)
3 Top crossbeam with guides	39.1 (38.0 as handled)
4 Jack	13.0 (typical)
5 Platen with sleeves	39.6
7 Rails, hinged extension and carriage	22.0 (rails 9.5, carriage 7.1)
8 Female mold with its steel base plate	36.5
9 Male mold	23.0
10 Male mold slide and crank	44.6 (stem 21.9, bracket 13.4, pin 4.5)
Press, items 1 to 10	344
12 QC rack	30.1
21 Interlock	3.9
16 Pump slot shield (with the guards)	2.8

The TRL 2 estimate of 180 kg was low, and solid molds would have weighed about 77 kg (female) and 52 kg (male); shells bring them to 22 and 23 kg. As fabricated, the heaviest part is the platen at 39.6 kg, inside R8's 40 kg with 0.4 kg to spare. The female mold is lifted as 36.5 kg with its base plate. Fully welded, the frame (items 1 to 3) would be one piece of about 165 kg that two people cannot move. As decided (PPR-DDR-001 item 12), the four upright joints are bolted, now with 4 x M16 10.9 each (PPR-DDR-004), so the frame arrives as a 34.2 kg base beam, an 8.9 kg jack plate, two 7.1 kg feet, two 29.4 kg upright pairs and a 38.0 kg top beam, and R8 is met on paper.

■ 11. Tipping

The press center of mass sits 6 mm in front of the frame center and 791 mm up. With the carriage, mold and charge slid 430 mm to the front it moves to 70 mm in front, well behind the front foot edge at 320 mm. The restoring moment is about 844 N·m, so a horizontal push of about 844 N at 1 m height would tip it forward. The feet are now anchored to the floor with four M12 anchors (PPR-DDR-004).

The rails are fixed to 290 mm in front of the axis and a 335 mm extension on two barrel hinges folds down inside the guards when the press is not being loaded or demolded (the hinge moved back 30 mm so the folded extension clears the gate and the lower front panel with the platen down, PPR-DDR-004). The press stands 940 x 700 mm inside its guards; the pump handle stands 158 mm outside the right guard while in use. That 158 mm is operating

space, like a door swing (decided by Amish, 2026-10-02), outlined on the floor in the general arrangement PPR-DWG-001 (Rev P6). With the carriage fully out, about 50.9 kg sits 140 mm past the hinge line, a moment of about 70 N·m that two stop lugs carry at about 2.9 kN each; tipped for demolding the lugs carry 10.8 kN each (section 4).

■ 12. Cost

Table 9. Cost by item, USD (matches `bom/bom.csv`).

Item	Cost	Item	Cost
1 Base, feet, jack plate, anchors	88	10 Slide and crank	101
2 Uprights with M16 bolts, tubes, shims	128	12 QC rack	47
3 Top crossbeam with guides	57	13 T-gauges	8
4 Jack	60	14 Buckets	16
5 Platen	51	15 Patterns	118
6 Springs	10	16 Fixed mesh guards and pump slot shield	73
7 Rails, hinged extension and carriage	41	17 Liners and trim tool	10
8 Female mold with steel base plate and dowels	119	18 Fasteners, consumables, finish	45
9 Male mold with bushes	102	19 Timer and thermometer	12
		20 Front gate with hinges	22
		21 Gate interlock and release extension	41

The press costs \$1,066 and the QC rack \$83, for **\$1,149**. Amish raised the budget from \$720 to \$930 on 2026-09-25 (PPR-DDR-001 item 14), topped it up to \$990 on 2026-09-26 (PPR-DDR-002 item 16), and raised it to \$1,060 on 2026-09-27 for the guarded version (PPR-DDR-003, option (a)), when R10 was met on paper at \$1,051. Making the design constructable (PPR-DDR-004) added \$92: the steel base plate under the female mold, the thicker 450 mm mold flanges, dowels and bushes (items 8 and 9, +\$44), floor anchors, the bolted jack plate and heavier feet (item 1, +\$22), the adapter disc and nut box (item 10, +\$9), interlock details (item 21, +\$7), and smaller changes elsewhere. The fixed inner shield behind the pump slot (decided by Amish on 2026-10-02) adds \$6: 2.8 kg of 2 mm sheet and flat bar at \$1.30/kg plus \$2 for bolts. Value-engineering target: USD 1,060. Estimated cost of the constructable design: USD 1,149 (USD 89 over the target), so **R10 is over the value-engineering target by \$89 (8.4 %)**. The target is a hypothetical control target and is not changed here; the design decisions register lists the cost drivers and savings worth trying (PPR-DDR-004, Q1). Guard solids are left out of the mass table in section 10, because the model draws their mesh at every eighth wire; the guards weigh about 45 kg (estimate), plus 2.8 kg for the pump slot shield, which is solid sheet and so is taken from the model.

■ 13. Results against the requirements

Table 10. Every requirement, by status (least certain first).

ID	Value	Target	Status
R2	±1.40 mm as cast; ±0.44 mm wall and ±0.44 mm coaxial when finished to templates, located by match-drilled dowels	±1 mm wall; 0.5 mm coaxial	At risk
R7	16 flat-back pattern segments for a 250 mm printer, no core boxes; no lathe needed (dowels, lapped stop faces); cavity hand finishing unproven	Printed patterns, hand and drill press finishing, no lathe over 300 mm swing	At risk
R9	Guards, gate and interlocks modeled (PPR-DDR-003); fixed inner shield behind the pump slot modelled. ISO 13857 desk check (section 15): side and rear mesh and the pump slot meet Table 4; front strips, lower front panel, front gate and roof mesh, the release shaft and pin cable openings and the top beam gap do not	Guards, interlocked gate, controls outside, pin in place and interlocked; openings to ISO 13857	Not met on paper until the proposed guard changes are made and the check is signed
R10	\$1,149 (press \$1,066, QC rack \$83), constructable design (PPR-DDR-004) with the pump slot shield	\$1,060 value-engineering target	Over the value-engineering target by \$89 (8.4 %)
R1	280 mm rim, 240 mm deep, 15 mm wall, 345 mm rim; 12.30 L brim, 9.91 L working; all from PARAMS	Reference filter from one source file	Met on paper
R3	No yield at 294 kN: 190 MPa beams, 272 MPa pin (yield 650), 54 MPa uprights, 117 MPa M16 joint bolts, 62 MPa male flange on the stop. Deflection 0.66 mm at 10 t (1.97 mm at 294 kN); molds close on a metal stop	No yield at 294 kN; under 1 mm deflection at 10 t	Met on paper
R4	5.2 min cycle; 69 pots per 6 h	6 min or less; 50 or more per 6 h	Met on paper
R5	310 mm opening against 270 mm needed (70 mm clear of the rim); 110 of 150 mm jack stroke	30 mm clear; press within one stroke	Met on paper
R6	4 stations; 1.69 mm per 0.1 L; 0.061 L per 1 mm reading error; 25 °C correction	0.1 L/h resolution, ±0.1 L/h repeatability	Met on paper (repeatability not verifiable at TRL 3)
R8	Heaviest part 39.6 kg (platen); frame bolted at the four upright joints, largest frame part 38.0 kg	40 kg or less	Met on paper
R11	Press 940 x 700 mm guarded with the rail extension folded (the pump handle stands 158 mm outside the right guard while in use), 1,806 mm tall; QC rack 780 x 780 mm	Press 1.0 x 0.7 m and 2.0 m; rack 0.8 x 0.8 m	Met on paper, at the 0.7 m depth limit
R12	Aluminum mold faces, polyethylene liners, HDPE buckets, no oils on molds; lead-free scrap alloy (decided)	Product-safe faces	Met on paper

Summary: 1 over the value-engineering target (R10), 1 not met on paper (R9), 2 at risk (R2, R7), 8 met on paper (R1, R3, R4, R5, R6, R8, R11, R12). R9 moved from at risk to not met on paper in v0.9, when the ISO 13857 desk check found openings short of the standard. In v0.8 the count was 3 at risk (R2, R7, R9) and 8 met; R9 had moved to at risk in v0.8, when Amish decided on 2026-10-02 that the 30 mm pump slot needs a fixed inner shield. In v0.7 the

count was 2 at risk and 9 met. In v0.5 the count was 0 not met, 2 at risk and 10 met. In v0.4 the count was 1 not met (R10), 2 at risk and 9 met; in v0.3 the count was 0 not met, 3 at risk and 9 met; in v0.2 the count was 1 not met (R10), 3 at risk and 8 met; in v0.1 the count was 3 not met (R3, R10, R11), 4 at risk and 5 met.

■ 14. Changes to earlier numbers

These TRL 2 figures in PPR-PRC-001 v0.2 and PPR-REQ-001 v0.2 disagreed with this note and are corrected in v0.3: pressed pot 7.3 kg (now 6.79), charge 8.0 kg (7.47), fired pot 4.2 kg (3.61), 1.0 L level drop 16 mm (16.7), 2.5 L drop 41 mm (42.6), base beam UPN 100 (now 2 x UPN 160), two 30 mm pins at 104 MPa (fail in bending; now one 60 mm pin), molds 20 and 12 kg (now 24 and 18 kg shells), press 920 x 640 x 1,655 mm and 180 kg (now 840 x 640 x 1,806 mm and 298 kg), cycle 5 min and 70 pots (5.2 min and 69), QC rack 800 x 440 mm for four stations (cannot fit; now 780 x 780 mm), cost \$716 (now \$926).

Changes in v0.2 (PPR-DDR-002): uprights bolted to both beams with 16 M20 8.8 bolts (item 2 cost \$77 to \$124); rails fixed to 320 mm in front of the axis with a 330 mm hinged extension (item 7 cost \$34 to \$45; press depth 970 mm to 655 mm with the extension folded); budget \$720 to \$930; total \$926 to \$984; R3 judged at 10 t (not met to met on paper); R8 (at risk to met on paper); R11 rack limit 0.8 x 0.5 m to 0.8 x 0.8 m (not met to met on paper).

Changes in v0.3 (budget top-up approved by Amish, 2026-09-26): budget \$930 to \$990; R10 not met to met on paper, \$6 (0.6 %) margin. `sizing.py` now prints the margin when the BOM is within budget.

Changes in v0.4 (guarded version, PPR-DDR-003): item 16 \$55 to \$67 (fixed mesh guards); new items 20 (\$21, front gate) and 21 (\$34, gate interlock and release extension); total \$984 to \$1,051; R10 met on paper to not met; R9 at risk to met on paper (guard openings assumed against ISO 13857, not checked); R11 judged on the guarded 940 x 700 mm envelope. `sizing.py` counts items 20 and 21 as press cost and leaves the guard solids out of the mass table.

Changes in v0.5 (cost overrun decided by Amish, 2026-09-27, PPR-DDR-003): budget \$990 to \$1,060; R10 not met to met on paper, \$9 (0.8 %) margin. No geometry, mass or cost figure changed.

Safety: These are paper calculations for a 20 t press. The single load pin is the one part whose failure ejects the male mold; it must be in place, fully home and interlocked before pressing. Nothing here replaces a proof load test by a competent person before use, which is TRL 4 work and on hold.

Changes in v0.6 (design for construction, PPR-DDR-004; Amish, 2026-09-30: "i accept your recommended changes on design that are currently being sent across for my approval"): beam gap 100 to 104 mm with shims; joint bolts M20 8.8 to M16 10.9 with spacer tubes (75 to 117 MPa); male flange 25 to 45 mm on a 450 mm diameter, now checked on the stop (487 to 62 MPa); pin block bearing 54 to 79 MPa (screw hole); stem lengthened to reach the plug floor (total deflection 0.61 to 0.66 mm at 10 t); new checks for the female base plate, the rails over the platen gap, the tipped mold, the stop lugs and the tipping pins; masses 298 to 344 kg for the press, heaviest part 38.9 to 39.6 kg; patterns 16 segments, 5.1 to 5.4 kg; QC rack 550 to 720 mm tall; cost \$1,051 to \$1,143, R10 within the value-engineering target to \$83 over it.

Changes in v0.7 (budget treated as a value-engineering target, 2026-10-01): R10 is reported against the \$1,060 value-engineering target, \$83 over, and no longer as a requirement that is not met. No number changed.

Changes in v0.8 (decisions of 2026-10-02): R9 met on paper to at risk until the pump slot shield is designed and the ISO 13857 desk check is signed; the working force is a process setting found in trials from about 2 t.

Changes in v0.9 (approved follow-ups, 2026-10-02): mean pressure at 2 t added to Table 3 (0.21 MPa); the pump slot shield is modelled and costed (item 16 \$67 to \$73, 2.8 kg; total \$1,143 to \$1,149, \$83 to \$89 over the target); the pump slot is lengthened from 220 to 272 mm so its ends stand 25 mm beyond the handle at the ends of its stroke; the ISO 13857 desk check is added (section 15); R9 at risk to not met on paper.

■ 15. ISO 13857 desk check of the guard openings

Decided by Amish on 2026-10-02: the check is done now, from the tables and the model's distances, signed by a competent person, and it is a hold point before any force above hand pressure. This section is the desk check. **It is not yet signed**; until it is, and until the openings that fall short are closed, nothing above hand pressure is allowed (build plan safety stop S8).

Method. For each opening, the opening size e and its kind (slot, square or round) give the safety distance s_r from ISO 13857:2019, Table 4 (upper limbs, persons 14 years and older), as read for this check: e up to 4 mm needs 2 mm; over 10 up to 12 mm, 100 mm for a slot and 80 mm for a square; over 12 up to 20 mm, 120 mm; over 20 up to 30 mm, 850 mm for a slot and 120 mm for a square; over 30 up to 40 mm, 850 mm for a slot and 200 mm for a square; over 40 up to 120 mm, 850 mm for every kind. The distance found is the straight line from the outer face of the opening to the nearest part that moves, with the press closed and open, measured on the model by `cad/src/model.py --iso` (called by `sizing.py`). The parts that move are the platen and everything it carries (rails, folding extension, carriage, female mold and pot) and the springs, moved by the jack, and the male mold and stem, moved by the crank. The load pin is moved only by hand with the press open and is left out. A real reach round an obstacle is longer than the straight line, so the distances are conservative.

Table 11. Openings against ISO 13857 Table 4.

Opening	Kind and size e	sr needed	Nearest moving part	Result
Mesh, right and left side guards	Square, 11.1 mm (12.7 mm pitch, 1.6 mm wire)	80 mm	110 mm, platen	Meets
Mesh, rear guard	Square, 11.1 mm	80 mm	100 mm, female mold	Meets
Pump slot with the fixed inner shield	Slot, 30 mm	850 mm	The slot opens only into the shield; no moving part enters the space inside it in any position	Meets: the shield encloses the reach
Mesh, front right strip	Square, 11.1 mm	80 mm	39 mm, folding rail extension	Does not meet
Mesh, front gate	Square, 11.1 mm	80 mm	44 mm, folding rail extension	Does not meet
Mesh, lower front panel	Square, 11.1 mm	80 mm	45 mm, folding rail extension (press open)	Does not meet
Mesh, front left strip	Square, 11.1 mm	80 mm	60 mm, folding rail extension	Does not meet
Mesh, roof guard	Square, 11.1 mm	80 mm	77 mm, stem (moved by the crank)	Does not meet
Release shaft opening, front right strip	44 mm square round a 12 mm shaft: slot-like gaps of 16 mm	120 mm	61 mm, folding rail extension (press open)	Does not meet
Pin cable opening, front right strip	Square, 40 mm	200 mm	166 mm, carriage	Does not meet
Top beam gap, 100 to 250 mm each side of the middle	104 x 150 mm, open from above between the guides and the uprights	850 mm	55 mm, stem (moved by the crank)	Does not meet
Top beam gap, 350 to 410 mm each side	104 x 60 mm, between the uprights and the end blocks	850 mm	215 mm, male mold (press open)	Does not meet

Pump slot and shield. The shield is a tunnel of 2 mm folded steel sheet, 30 mm wide inside, from the slot along the handle's line to 3.0 mm off the jack body, with a flange bolted through the slot frame and a flat-bar stay to the base beam. Through the slot only the pump handle and the end of the jack's pump socket can be reached; the platen, molds, springs and ram are behind steel, the nearest of them 51 mm outside the shield. The handle runs 5 mm from the side walls over its whole stroke, a sliding pass with no closing gap. The slot was lengthened from 220 to 272 mm, and the tunnel's roof and floor follow the handle, so that at both ends of the stroke the handle stops 25 mm short of the slot ends and of the roof and floor (ISO 13854 gives 25 mm as the minimum gap that does not crush a finger). The 3 mm gap between the tunnel and the jack body is between fixed parts.

The pump handle passing the slot frame. The handle crosses the guard at 25 degrees and passes the sides of the slot frame at 2.3 mm at the ends of its stroke, closer near mid-stroke, moving along the slot. A gap of 4 mm or less does not admit a fingertip (Table 4, first row), so this pass is not a finger shear point on paper; the competent person should confirm it on the jack bought, since the handle's own play sets the real gap.

Roof reach. The roof mesh stands 28 mm above the top beam, with its cut-out 5 mm clear of the beam all round. The top beam itself is open from above between its two channels wherever nothing fills the gap: from the stem guides to the uprights (104 x 150 mm each side) and from the uprights to the end blocks (104 x 60 mm). An arm

reaching through these meets the stem, and, with the male mold cranked up, the male flange, which then stands 15 mm under the top beam: both moved by the crank, not the jack, but a 15 mm gap closed by a self-locking screw is a crush point. Above the roof, the stem's cap plate rises to 10 mm under the crank bracket's top plate at full lift, inside a bracket open at the front and back.

Findings and proposed changes (awaiting Amish; see the design decisions register).

1. Finer mesh on the front strips, lower front panel, front gate and roof: 6.35 mm (1/4 in) welded mesh with 0.9 mm wire is about 5.5 mm clear, which needs 5 mm (square, over 4 up to 6 mm), so every front and roof distance above meets. Moving the front panels out by 41 mm instead would break the 0.7 m depth of R11.
2. Close the release shaft and pin cable openings to a 4 mm gap or less: a bolted plate with a 20 mm hole round the 12 mm shaft, and a grommet plate with a 10 mm hole for the 6 mm cable.
3. Cover plates of 3 mm steel over the four openings in the top beam gap, bolted to the top flanges, so the roof reach meets only fixed steel.
4. Close the open front and back of the crank bracket with mesh or sheet, so the stem's cap plate cannot be reached as it rises under the bracket's top plate.

With all four, every opening in Table 11 meets ISO 13857 Table 4 on paper (about USD 15 in parts, estimate). The check then needs the competent person's review against the published tables and signature.

Desk check	Name	Signature	Date
Prepared from the model	Amish Chadha (calculation note author)		2026-10-02
Checked and signed by a competent person		Not yet signed	